

NEVADA TRANSPORTATION CONFERENCE APRIL 15, 2015

Pedro Rodriguez, P.E.

Nevada Department of Transportation

Project Manager


Brian Graham

Q&D Construction, Inc.


Project Manager

TOGETHER, we're making the grade.

CMAR GENERAL



OPINION OF PROBABLE CONSTRUCTION COST










GOOD CANDIDATE FOR CMAR?



























































DEFICIENT PAVEMENT



Annual patching - Bad reputation







NATURAL SPRINGS














QUEUING AND POOR SIGHT DISTANCE

Left turn causes long queuing at Tramway Dr.









QUEUING AND POOR SIGHT DISTANCE

Poor sight-distance at Tramway Dr.







POOR PEDESTRIAN VISIBILITY

No existing lighting at crosswalk









POOR PEDESTRIAN VISIBILITY

No existing lighting at crosswalk









SIDEWALK, C&G, & ADA














MANY UTILITIES









FINAL SCOPE OF WORK

- 13-inch full-depth reconstruction
 - Rehabilitate and repave existing roadway
- Water quality improvements
 - Improve roadway drainage and water runoff
- Other improvements







GOOD CANDIDATE FOR CMAR!

- Design 30% complete
- Env. clearance work minimal
- R/W acquisition minimal
- Funding already identified
- Project required:
 - Risk identification
 - Detailed MOT plan
 - Constructability review
 - Innovation
 - Major public outreach









LET'S GET TO WORK!

- CMAR and ICE were procured
- Public outreach began immediately
 - Barrett Resources & Bauserman Group
- Design progressed with CMAR at table
- OPCC's prepared and risks were mitigated
- MOT continuously discussed
- Innovation was applied







- Risks and Innovation
 - What were the risks?
 - How were they mitigated?
 - What innovation was applied?







RISKS IDENTIFIED

- 3-year construction due to short seasons
- MOT Minimize commuter disruption
- Special events and holidays
- Weather
- Environmentally sensitive area
- Erosion control
- Unknown utilities
- Limited staging areas







INNOVATION APPLIED

- Roadbed modification
 - GPR verification that roadbed mod method was feasible
- Extensive public outreach
 - Regular stakeholder input & coordination with casinos
- Night Work Allowed in Residential Area
- MOT Marathon paving summit closures








- Final MOT 1 ½ Year Schedule
- Before Memorial Day and <u>after Labor Day</u>
 - Day and Night Work Shifts
 - Work 24 hours per day 6 days per week
 - 24/7 Traffic Control
 - Access to all from US 50
 - Summit closure
 - Emergency vehicles and buses
















- Between Memorial Day and Labor Day
 - Night work only
 - Night work will have one lane alternating traffic only
 - During the day, one lane will be open in each direction
 - Full access over the summit















GMP REACHED

- Awarded to Q&D Construction with a GMP of \$14,877,619.22
- Anticipated construction completion was July 3, 2015







LAST MINUTE REVISION

- Negative publicity due to Public information meeting in Carson Valley
- Concerns
 - Candy Dance
 - Summit traffic vs. through traffic
- Gate option introduced
- Benefit realized less traffic thru job site







CONSTRUCTION PHASE

- RISKS REALIZED
 - Late snow fall
 - Fire
 - Storm event
 - Erosion
 - Unknown utilities
 - Special events / Acess







CONSTRUCTION PHASE

- 5,900 LF of new storm drain pipe
- 8,600 LF of curb and gutter
- 21,000 tons of asphalt
- Over 85,000 man-hours
- Average of 60 workers







OUTCOME

- Early completion!
 - Substantially complete by October 2014
- Numerous compliments!
- NDOT reputation restored!
- Under budget!

GO CMAR!







QUESTIONS?





