

## **Presentation Overview**

- Risk and Opportunity Associated with a Percent Within Limits (PWL) Specification
- Evolution of Specifications
- Overview of Percent Within Limits (PWL)
- Opportunities/Risks of a PWL Specification to a Contractor
- Critical Components of a PWL Based Specification
- Understanding Agency/Contractor Return on Investment

## **Evolution of Specifications**


AASHO Road Test (Late 1950's)

- Basis of AASHTO Pavement Design Guide
- Collected "Real Time" Test Data and Quantified
  - Variability of Material Properties
  - Variability of Construction Practices



- AASHO Road Test Lessons Learned:
  - Specification Tolerances Must Recognize Total Variability of Materials Properties and Construction Practices
  - Specification Limits Must Apply Reasonable Risk to Both the <u>Seller</u> and <u>Buyer</u>

## What is PWL? Statistics – Ugh...




Percentage of cases in 8 portions of the curve

Standard Deviations Cumulative Percentages

Percentiles

in Stanine

Z scores
T scores
Standard Nine
(Stanines)
Percentage



## **Percent Within Limits Specification**

#### What is It?

- Statistically Based Acceptance and Payment
- Assumes Material Production Test Data Follows a Normal Distribution (i.e. Bell Curve)
- Considers the Following For Acceptance:
  - Population Average and Standard Deviation (i.e. multiple samples)
  - Design Target and Specification Limits
- Rewards Being on Target and Being Consistent
- Acknowledges Level of Quality Different when Process is Off Target or Too Variable
- Acceptance and Payment Adjusted Based on Proximity to Design Target and Variability

## Percent Within Limits (PWL) Specification


What is It?

PWL = Area of Distribution within Spec Limits

PD = Percent Defective

 $PWL = 100 - (PD_U + PD_L)$ 

PWL Then Converted to \$ with Pay Adjustment Table



## **PWL Specifications**


#### General

- Not All PWL Specifications Are the Same
  - Mechanics of Statistical Calculations Are the Same But Acceptance/Payment Processes Differ
- Acceptance and Payment Differences
  - Contractor Data For Acceptance/Payment with Agency Statistical Check
  - Agency Data Acceptance/Payment but Require Contractor Data Be Submitted
  - Agency Data Acceptance/Payment Only Require Contractor Data For Dispute Process
- For This Presentation
  - General Discussion of What We Have Learned From Experiences in Multiple States
  - Focus on HMA PWL Specifications

### Percent Within Limits vs. Other Acceptance Criteria

#### What's The Difference?

- Conformance to Specification Acceptance Criteria
  - Non Statistically Based Acceptance
  - Considers Only Specification Limits Only For Acceptance
    - Between Limits = Acceptance
  - Individual Sample Measure
  - Level of Quality Assumed to Be The Same for All Tests within Specification Limits
  - Acceptance and Full Pay Awarded for Being in Anywhere with Specification Band



# PWL Specification Signals a Significant Change in Opportunity/Risk to a Contractor

- Not Business as Usual
- Being In Specification is No Longer Good Enough
- Requires Operational Planning
  - Those Who Do Not Prepare Often Struggle On Initial PWL Projects
- May Require Changes to:
  - Production Equipment
  - Products
  - Laboratory Facilities and Equipment
  - Quality Control Staff



## Opportunities/Advantages



## **PWL Specifications**

#### Key Opportunities/Advantages

- PWL Acceptance Criteria is Best Tool to Quantify Quality
  - Considers TV, Spec Limits, Average, Variability
- QC/QA with PWL Acceptance
  - Transfer of Responsibility/Risk from Agency to Material Producer/Contractor for Quality
- Opportunity for Producer/Contractor to Control Processes
- Opportunity to Be Compensated for Quality Provided
- Opportunity for Producer/Contractor to Refine Processes and Build Technical Competency

# Opportunities/Advantages Transfer of Responsibility With QC/QA

- Take Greater Role in Design and Acceptance Testing
  - Perform Own Mix Designs with Agency Verification Process
  - QC Data Used as Part of Acceptance and In Some Locations Payment
- Led to Investments In:
  - Facilities
  - Equipment
  - Technical Personnel
  - Laboratory AASHTO Accreditation (14 AASHTO Accredited Laboratories)
- Outcome
  - Improved Materials Quality
  - Increased Technical Competency



Before QC/QA Specifications (early 2000's)









After QC/QA Specifications (2019)

## Opportunities/Advantages

**Compensated for Quality** 

- Incentives/Disincentives Pay Factors
- All Businesses Strive to Maximize Profits
- Driver for Improved Quality



## **Opportunities/Advantages**

Refine Processes and Build Technical Competency

- Preparation for Future Contracting Practices
  - Construction Manager at Risk (CMAR)
  - Design/Build
  - Design/Build/Maintain
  - Warranty

- Complimentary Benefits
  - Materials Optimization for Cost and Quality
  - Development of Byproduct Uses



**Building Value Together** 

Lack of Knowledge of Risk in Specifications

- Applies to Both Industry and Agency
- Risk and Payment Changes with:
  - Lot and Sublot Size
  - Samples and Tests per Lot and Sublot
  - Sampling Location
  - Test Methods and Test Method Options
  - Acceptance Limit Changes
  - Specification Limit Changes
  - Pay Factor Equations, Weights and Variables
  - ...
- Full Risk Impact of PWL Spec Often Only Understood During/After First Projects


#### Not Being Prepared for the Change


- A Contractor Must have a PWL Implementation Plan That Considers:
  - Evaluation of Existing Mixes Are Changes Required to Achieve Desired Level of Bonus?
  - Operational Changes that Cost \$\$\$
  - Laboratory Facilities, Equipment and Accreditation
  - Quality Control Staff
  - PWL Specification Training Within Organization
- This Can Be a Big Opportunity Also!!!



## **Production Team Training Example**

**Understanding Targets and Variability** 





**Impact of Being More Variable** 

**Impact of Being Off Target** 

#### Laboratory Accreditation

- Accreditation Matters
  - Round Robin Studies Confirm Reduced Variability in Data From Accredited Labs
  - Recognized by Many Agencies Requiring Design Labs Be Accredited
- Does a Double Standard for Accreditation Exist?
  - Non Design Labs Typically Not AASHTO Accredited But Perform Significant Amount of Acceptance Testing
  - What is Impact on Mix Design Verification and Production Acceptance/Payment?



## Critical Components of a PWL Based Specification

- Contractor Participation in Design and Production Acceptance Processes
- Risk Based Specification Limits
- Test Turnaround Timelines
- Dispute Resolution Process
  - Including Outlier Identification and Re-Testing Provisions

## Contractor Participation in Design and Production Acceptance Processes

- Increased Contractor Participation in Material Design/Testing is Important Part of Assuming Additional Risk
  - Mix Design
    - Agency Transfers Risk to Contractor and Have Contractor Perform the Design
    - Contractor Assumes Risk of a "Good" Design
    - Contractor Develops Mix Design to Meet Agency Requirements
    - Agency "Verifies" Mix Design on Lab or Field Produced Material
  - Production Acceptance
    - Contractor Data Required and Considered in Acceptance Process
- Without Increased Participation Will Contractor Capabilities/Quality Improve?

## **Risk Based Specification Limits**

- Define <u>Acceptable and Unacceptable</u> Material Quality
- Must Incorporate All Sources of Variability
  - Function of  $(S^2_T) = S^2_{\text{sampling}} + S^2_{\text{testing}} + S^2_{\text{material/construction}}$
- Specification Limits Basis:
  - Acknowledge Sampling and Testing Variability in Spec Limit Development
  - Review Historical Data to Understand Overall Variability
  - Consider Buyers and Sellers Risk

## **Risk Based Specification Limits**

Buyer's Risk β = Risk of Accepting "Bad" Material


Seller's Risk  $\alpha$  = Risk of Rejecting "Good" Material

FHWA Recommended Seller's Risk (α): 5.0% Max.

> Typically 2s About the Mean

#### Sellers Risk

(With ± 0.4% Tolerance)



# Test Turnaround Timelines and Data Management

- Timely Test Data Critical for PWL Specification
  - Data Required for Timely Plant Changes/Process Changes
  - PWL Process Requires Proactive Plant Changes to Achieve Bonus
  - Use of Testing Software Critical with Automated Data Reporting Capabilities
- QC vs. QA Testing
  - Often Differences Exist Between the QC and QA Results
  - Need to Understand and Quickly Resolve Between Lab Differences
  - Highest Risk Start of Project

## **Proactive Information Dissemination**

Right Information, Right Level of Detail, Right Person at the Right Time


#### **Automated Sample Specific Email Alerts**


From: Benkovich, Teilhard Sent: Monday, May 21, 2018 2:05 PM To: Subject: StonemontQC Email Alert

| Sample Information |                                    |  |  |  |  |  |
|--------------------|------------------------------------|--|--|--|--|--|
| Plant              | 100186- Plant#1                    |  |  |  |  |  |
| Product            | 1817-3/4" AGGREGATE BASE           |  |  |  |  |  |
| Sample Id          | 1851358776                         |  |  |  |  |  |
| Sampled Date       | 5/21/2018 7:59:00 AM               |  |  |  |  |  |
| Sampled By         | Ty Benkovich                       |  |  |  |  |  |
| Sample Type        | Process Control                    |  |  |  |  |  |
| Sample Method      | Stockpile                          |  |  |  |  |  |
| Sample Location    | West Plant                         |  |  |  |  |  |
| Ledge              | 134B - 1" and 3/4" PMA w/ agg base |  |  |  |  |  |
| Sample Notes       | PRODUCTION 5/21/18                 |  |  |  |  |  |
| User               | tbenkovich                         |  |  |  |  |  |

| Sieve | Mass Retained | % Passing | Specifications | Targets | Comment |  |  |
|-------|---------------|-----------|----------------|---------|---------|--|--|
| 1"    | 0.00          | 100       | 100-100        |         |         |  |  |
| 3/4"  | 48.10         | 98        | 90-100         |         |         |  |  |
| 1/2"  | 467.20        | 77        |                |         |         |  |  |
| 3/8"  | 260.70        | 65        |                |         |         |  |  |
| #4    | 501.80        | 42        | 35-65          |         |         |  |  |
| #8    | 359.60        | 26        |                |         |         |  |  |
| #10   | 35.60         | 24        | 25-53          |         | Fail    |  |  |
| #16   | 101.80        | 20        | 15-40          |         |         |  |  |
| #30   | 100.40        | 15        |                |         |         |  |  |
| #40   | 44.40         | 13        | 12-28          |         |         |  |  |
| #50   | 48.10         | 11        |                |         |         |  |  |
| #100  | 67.40         | 8         |                |         |         |  |  |
| #200  | 38.60         | 6.3       | 2-10           |         |         |  |  |
| PAN   | 10.60         | 0.0       |                |         |         |  |  |

#### **Automated Summary Reporting**





#### **Statistical Summary Reports**

#### GRADITE

| Sample Id  | Date             | AC                     |        | Specimen          |                       | Vtotal (%) | Absorption                     |                             | Spgr                        | SPGR                  | Density                      | UnitWt                              | UnitWt                       |
|------------|------------------|------------------------|--------|-------------------|-----------------------|------------|--------------------------------|-----------------------------|-----------------------------|-----------------------|------------------------------|-------------------------------------|------------------------------|
|            |                  | Conte<br>(Pb) (S       |        | Thickness<br>(in) | (Va) (%)              |            | (Asphalt)<br>(%)               | (Compact ed,Gmb)            | (Effective,<br>Gse)         | (Max,<br>Gmm)         | (Relative)<br>(%)            | (Compact ed) (Ib/ft3)               | (Max)<br>(lb/ft3)            |
| 1805954198 | 04/06/2018 07:30 | 5.16                   | 1176.6 | 2.462             | 5.0                   | 0.120      | 0.31                           | 2.357                       | 2.693                       | 2.482                 | 95.0                         | 146.7                               | 154.5                        |
| 1816628351 | 04/30/2018 09:00 | 5.66                   | 1184.3 | 2.469             | 4.4                   | 0.132      | 0.28                           | 2.356                       | 2.695                       | 2.465                 | 95.6                         | 146.7                               | 153.4                        |
| 1949783582 | 05/04/2018 06:15 | 5.09                   | 1217.6 | 2.602             | 6.6                   | 0.116      | 0.32                           | 2.314                       | 2.680                       | 2.475                 | 93.4                         | 144.0                               | 154.1                        |
| 1951697511 | 05/09/2018 07:30 | 5.32                   | 1219.8 | 2.594             | 6.8                   | 0.120      | 0.39                           | 2.310                       | 2.694                       | 2.478                 | 93.2                         | 143.8                               | 154.3                        |
| 1851357891 | 05/11/2018 08:00 | 5.27                   | 1213.0 | 2.557             | 6.0                   | 0.120      | 0.46                           | 2.338                       | 2.702                       | 2.486                 | 94.0                         | 145.5                               | 154.8                        |
| 1709315668 | 05/16/2018 09:15 | 5.31                   | 1219.5 | 2.549             | 4.9                   | 0.123      | 0.22                           | 2.368                       | 2.709                       | 2.490                 | 95.1                         | 147.4                               | 155.0                        |
| 1486992342 | 05/21/2018 08:20 | 5.18                   | 1202.0 | 2.526             | 5.4                   | 0.120      | 0.22                           | 2.358                       | 2.705                       | 2.492                 | 94.6                         | 146.8                               | 155.2                        |
| 1478535197 | 05/29/2018 08:10 | 5.23                   | 1201.4 | 2.482             | 4.8                   | 0.121      | 0.36                           | 2.362                       | 2.695                       | 2.482                 | 95.2                         | 147.0                               | 154.4                        |
| 1886037192 | 05/30/2018 08:30 | 5.50                   | 1206.2 | 2.533             | 5.0                   | 0.126      | 0.44                           | 2.340                       | 2.685                       | 2.464                 | 95.0                         | 145.6                               | 153.4                        |
| 1536175826 | 06/12/2018 07:30 | 5.00                   | 1197.2 | 2.502             | 5.7                   | 0.115      | 0.20                           | 2.350                       | 2.697                       | 2.492                 | 94.3                         | 146.2                               | 155.2                        |
| 1584052079 | 06/19/2018 06:40 | 5.52                   | 1219.8 | 2.552             | 4.4                   | 0.127      | 0.14                           | 2.350                       | 2.681                       | 2.460                 | 95.6                         | 146.3                               | 153.2                        |
| 1667657298 | 06/19/2018 08:00 | 5.27                   | 1210.2 | 2.562             | 4.9                   | 0.121      | 0.28                           | 2.344                       | 2.674                       | 2.464                 | 95.1                         | 145.8                               | 153.4                        |
| 1991024109 | 06/19/2018 10:10 | 5.14                   | 1209.8 | 2.525             | 4.7                   | 0.119      | 0.18                           | 2.364                       | 2.688                       | 2.480                 | 95.3                         | 147.2                               | 154.4                        |
| 1596150320 | 06/20/2018 05:45 | 5.04                   | 1220.5 | 2.530             | 4.6                   | 0.117      | 0.13                           | 2.370                       | 2.691                       | 2.486                 | 95.4                         | 147.6                               | 154.8                        |
| 1093338125 | 06/20/2018 08:15 | 4.65                   | 1198.9 | 2.480             | 3.6                   | 0.109      | 0.13                           | 2.392                       | 2.666                       | 2.480                 | 96.4                         | 148.9                               | 154.4                        |
| 1536175433 | 06/21/2018 06:00 | 5.05                   | 1208.0 | 2.520             | 3.8                   | 0.117      | 0.16                           | 2.358                       | 2.650                       | 2.452                 | 96.2                         | 146.8                               | 152.6                        |
|            |                  | AC<br>Conte<br>(Pb) (9 |        |                   | Air Voids<br>(Va) (%) | Vtotal (%) | Absorption<br>(Asphalt)<br>(%) | SPGR<br>(Compact<br>ed,Gmb) | Spgr<br>(Effective,<br>Gse) | SPGR<br>(Max,<br>Gmm) | Density<br>(Relative)<br>(%) | Unit Wt<br>(Compact<br>ed) (lb/ft3) | Unit Wt<br>(Max)<br>(Ib/ft3) |
|            |                  | Count 16               | 16     | 16                | 16                    | 16         | 16                             | 16                          | 16                          | 16                    | 16                           | 16                                  | 16                           |
|            |                  | Mean 5.21              | 1206.6 | 2.528             | 5.0                   | 0.120      | 0.26                           | 2.352                       | 2.688                       | 2.477                 | 95.0                         | 146.4                               | 154.2                        |

0.0053 0.109 0.0203 0.0151 0.0122 0.89

St Dev 0.238 12.88 0.0415 0.89




# Dispute Resolution Best Practice

- Process Needs to Be Well Defined
- Consider both QC and QA Data
- Utilize Independent 3<sup>rd</sup>
   Party Resolution Testing
   Labs Mutually Agreed
   Upon
- Utilize a Simple Process as to Promotes Timely Resolution of Issues

## **Dispute Resolution**

#### **Outlier Detection and Re-Testing**

- Need for Outlier Definition "Wacky or Flyer"
- Need for Outlier Detection Tool
  - ASTM E178 or some other criteria
- Need Re-test Provision Test whole sample or individual test? Split or independent sample…
  - Just Because Something Is Out of Specification, Does Not Mean It Should be Re-Tested



## Return on Investment (ROI)

#### **Contractor**


- Return on Investment (ROI)
  - Investment Made to Improve Quality and Increase Bonus Payment
    - Facilities, Equipment, Technical Personnel
- Assume Reasonable Return on Investment
  - Significant Capital Investments Required
  - Bonuses Must Exceed Investments
  - Must Consider Long Analysis Period
  - Specification Must be Steady-State




## Return on Investment (ROI)

#### Agency

- Does Bonus Payout Result in Sufficient Increased Quality/Performance?
- Are Expenditures Within the Context of Quality and Consequence of Failure
  - Identify and Optimize Agency Expenditures on Items with Greatest Consequence of Failure (e.g. Bridge Deck vs. Frontage Road)





## Summary

- PWL Specifications Provide Both an Opportunity and Increased Risk to a Contractor
- As Part of a Contractor Assuming More Risk, Agencies Typically Transfer Additional Responsibilities to the Contractor (i.e. mix design, use of QC Data in acceptance process)
- Contractors Must Prepare and Evaluate Impact to "Current" Operations
  - Budget for Changes to Facilities, Equipment, Staff and Operations
  - Those Who Do Not Prepare Will Struggle
- Specification Limits Must be Developed Considering Both Buyers and Sellers Risk
- Return on Investment Well Designed PWL Specification
  - Contractor Achievable Bonus Must Be Sufficient to Cover Initial Investments
  - Agency Increased Level of Quality and Performance to Justify Bonus

